

RECEIVED

NOV 29 1983

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-007-20378-0000

API NUMBER 20378 - 007

FILE ROOM

LEASE NAME J.T. Marsh Trust

TYPE OR PRINT

WELL NUMBER #1

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

SPOT LOCATION 230' ENL 330' FEL

LEASE OPERATOR Santa Fe Andover Oil Company (Andover Oil Company)

SEC. 21 TWP. 32 RGT. 15 () OR (W)

ADDRESS P.O. Box 45485/Tulsa, Oklahoma 74147

COUNTY Barber

PHONE #(918)262-8510

OPERATORS LICENSE NO. 8873

DATE WELL COMPLETED 2-26-76

PLUGGING COMMENCED 11-16-83

CHARACTER OF WELL oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 11-19-83

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACG-1 FILED? yes IF NOT, IS WELL LOG ATTACHED?

PRODUCING FORMATION Mississippi Chat DEPTH TO TOP 4872 BOTTOM 4884 T.D. 5,000

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Miss. Chat	Oil	4872	84	8 5/8	210	-0-
				4 1/2	5000	3036

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. 11-16-83 Pumped 1 sx hulls pumped 25 sx cement to 4765 ft. Displaced plug with 9.5# mud 11-18-83 Loaded hole with 9.5# mud. Pumped 60 sx cement plug from 900 to 650 ft. Loaded hole with 9.5# mud. Pumped 65 sx cement from 400 to 150 ft. Loaded hole with 9.5# mud Pumped 15 sx cement plug from 5 to 45 ft. 11-19-83 welded steel plate with anem and date on top.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Jerry Dunkin Casing Pulling, Inc.

LICENSE No. 8733

ADDRESS P.O. Box 389/Enid, Oklahoma 73702

STATE OF _____ COUNTY OF _____, SS.

Dennis Davis

(EMPLOYEE OF OPERATOR) OR

(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL WAS FILED WITH THE STATE OF KANSAS AND IS CORRECT, SO HELP ME (GOD).

(SIGNATURE) *Dennis Davis*

(ADDRESS) P.O. Box 1128, El Reno Oklahoma

EL RENO FILE ROOM

DEC 6 1983

SUBSCRIBED AND SWORN TO BEFORE ME THIS 23 DAY OF November, 1983

Diane Rowley
NOTARY PUBLIC

MY COMMISSION EXPIRES: 4-28-85

Wichita, Kansas
CONSERVATION DIVISION

FORM (P-4)
REVISED 01-83

RECEIVED
STATE CORPORATION COMMISSION
JAN 1 0 1984
1-1-84