


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 34 Twp. 32 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C NE NE NE
Lease Owner Raymond Oil Co., Inc.
Lease Name Hildebrand #8 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/22/77 _____ 19____
Plugging completed 7/1/77 _____ 19____
Reason for abandonment of well or producing formation _____
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____ yes

Name of Conservation Agent who supervised plugging of this well Metz
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4945
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8	480	none
				5 1/2"	4943'	3813'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4850' and set 5 sacks cement. Shot pipe at 3940', spotted 40 barrels oil. Shot pipe at 3800', 2600', pulled 117 joints. Set rock bridge at 280' and ran 5 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1977
7-11-77
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Walter Voth

CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of July, 19 77

My commission expires

NOTARY PUBLIC
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

Margaret Melcher
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

412 Union National Bldg., Wichita, Kansas

15-007-10136-0000

COPY

Company - CHAMPLIN OIL REFG. CO.
Farm - Hildebrand No. 8

SEC 34 T. 32 R. 15W
NE₄ NE
350' E Line 530' E EL-NE₄

Total Depth. 4945'

Comm. 10-27-46

Shot or Treated.


Contractor.

Issued. 3-15-47

Comp. 11-23-46

County. Barton

KANSAS



CASING:

9 5/8"
5 1/2"

480' cem.w/250 sx.
4948' cem.w/150 sx.

Elevation.

Production Pot. 1609 Bbls. plus
35% wtr.

Figures Indicate Bottom of Formations.

shale & shells	0-483
shale & red bed	870
shale & shells	2180
lime & shale	2235
lime, shells & gyp	2345
lime sdy & shale	2390
lime & shale	2490
lime sdy	2520
lime brkn & shale	2590
shale & lime	3360
shale & lime brkn	3440
lime & shale	4215
lime & chert	4285
lime & shale	4320
lime	4420
cherty lime	4520
lime	4545
shale & lime	4595
lime	4610
lime & shale	4690
lime	4720
lime & shale	4840
lime	4890
shale & lime	4935
lime & chert	4945
Total Depth	

Tops:

Kansas City	4165
Base, Pennsylvanian	4710
Viola Section	4875
Coarsely crystallized-	4888

RECEIVED
STATE CORPORATION COMMISSION

JUN 02 1977
6-2-77
CONSERVATION DIVISION
Wichita, Kansas