


STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21, 743 

LEASE NAME De Geer

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1-34

230 Ft. from S Section Line

230 Ft. from E Section Line

SEC. 34 TWP. C SW NE 32 SRGE. 15 (X or (W))

COUNTY Barber

Date Well Completed 3-1-84

Plugging Commenced 11-21-89

Plugging Completed 11-29-89

LEASE OPERATOR Vincent Oil Corp.

ADDRESS 125 North Market #1110 Wichita, Ks 67202

PHONE# (316) 262-3573 OPERATORS LICENSE NO. 5004

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Nov. 20, 1989 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Marmaton Depth to Top _____ Bottom T.D. 5250

Show depth and thickness of all water, oil and gas formations. PBTD: 4960 Perfs: 4735-39
 4747-51

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	833	8 5/8	833	0
		0	5236	4 1/2	5236	2625'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
 Bottom hole plug: 1 sx. hulls and 30 sx. cement, tagged cement at 4264' Cut off casing, and pulled 2625' of 4 1/2, 64 joints.

Top hole plug: 400# hulls, 10 gel, 50 sx. cement, 10 gel, 100# hulls, 8 5/8 plug, 100 sx. cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 55025893

Address P.O. Box 847 Pratt, Kansas 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vincent Oil Corp.

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of ~~Pratt Well Service, Inc.~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed thereon are true and correct, so help me God.

(Signature) Judy Berry
 (Address) PO Box 847 - Pratt, Ks. 67124



SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 89

Dorothy M. Furgason
 Notary Public

My Commission Expires February 6, 1989