


WELL PLUGGING RECORD

Give All Information Completely
Info. Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

County. Sec. Twp. Rge. (E) (W)
Location as "NE/CNW&SWK" or footage from lines 33 32 15
Lease Owner Barber C/NW NW
Lease Name Time Petroleum Company Well No. _____
Office Address DeGeer 1
Character of Well (Completed as Oil, Gas, or Water) 815 Union National Bldg. Wichita, Kansas
Date well completed Dry Hole 19____
Application for plugging filed December 23 19 61
Application for plugging approved December 23 19 61
Plugging commenced December 23 19 61
Plugging completed December 23 19 61
Reason for abandonment of well or producing formation December 23 61
Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. LaCamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	13-3/8"	0	203'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 190' with 30 sacks of cement, 1/2 sack of hulls and mud to 30'; plugged at 30' with 10 sacks of cement. Job completed at 9:15 A. M. December 23, 1961.

RECEIVED
STATE CORPORATION COMMISSION

IAN 4 1962
1-4-62
CONSERVATION DIVISION
Wichita

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.
Ralph Schuyler (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Schuyler
Ralph Schuyler
Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 19 61

My commission expires December 14, 1965

Elaine H. Taylor
Notary Public.



D R I L L E R S L O G

#1 DeGeer "A"

CASING RECORD: 203' of 13-3/8" surface casing
 COMPANY: Time Petroleum Company
 CONTRACTOR: Strata Drilling, Inc. DESCRIPTION: C/NW NW Section 33-32-15W Barber County, Kansas

TOTAL DEPTH: 5183'
 COMMENCED: December 6, 1961
 COMPLETED: December 23, 1961

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Gyp & Red Bed	0	65	Ran 203' of 13-3/8" surface casing; set and cemented at 203' with 80 sacks of cement, 2% gel and 2% C. C. Plug down at 11:55 P. M. December 7, 1961.
Red Bed	65	203	
Red Bed & Shale	203	1100	
Shale & Shells	1100	1765	
Shale & Lime	1765	2460	
Lime	2460	2570	
Lime & Shale	2570	2960	
Shale	2960	3185	
Shale & Lime	3185	4179	
Lime	4179	4740	
Lime & Chert	4740	4789	
Lime	4789	4808	
Lime & Shale	4808	4868	
Lime	4868	4938	
Lime & Shale	4938	4998	
Lime	4998	5030	
Lime & Chert	5030	5052	
Lime	5052	5107	
Lime & Shale	5107	5145	D. & A.
Shale & Sand	5145	5178	
Lime & Shale	5178	5183	

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 14 1963
 2-14-63
 CONSERVATION DIVISION
 Topeka, Kansas

Total depth 5183'

Hole plugged as follows: Plugged at 190' with 30 sacks of cement, 1/2 sack of hulls and mud to 30'; plug at 30' with 10 sacks of cement. Plug down at 9:15 A. M. December 23, 1961.

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Ralph Schuyler
 Ralph Schuyler

Subscribed and sworn to before me this 26th day of December, 1961.

Elaine H. Taylor
 Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965