



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 27 1953  
 2-27-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Albert Schiffner of Forbes Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Schiffner guarantees payment of the plugging fee.

Operator's full Name: Tompson and Bear

Complete Address: 335 Union Center Bldg., Wichita, Kansas

Lease Name: Eads Well No. # 2

Location: SW NE NE Sec. 4 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4554 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Schiffner was instructed to plug the well as follows:

264' of 8.5/8" surface pipe cement circulated. 4549' of

5 1/2" long string cemented with 75 sacks. Perferated from

4528' to 4532'. Sanded to 4515' cemented with 5 sacks.

Fill hole to 200' with mud, set 10' rock bridge, cement

with 20 sacks. Fill to 40' with mud and 10' rock bridge

cemented with 10 sacks to base cellar.

Very truly yours,

Archie Elving  
 Conservation Division Agent