



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 20 1962

12-20-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. T. L. Dix of Skelly Oil Co. has this date requested permission to plug the following described well:

Mr. T. L. Dix guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Co. Box 1650 Tulsa, Okla.

Complete Address: Box 1650 Tulsa, Okla.

Lease Name: M. H. Eubanks Well No. # I

Location: C - NW - NW Sec. 4 Twp. 30S Rge. 14(E) (W) W

County Barber Total Depth 4740 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. T. L. Dix was instructed to plug the well as follows:

789' of 8 5/8" surface pipe circulated with cement. Hole filled with heavy drill mud to 300', 1/4 sack hulls, first cementing plug, 1/4 sack hulls and rock to hold weight of drill pipe, and 20 sacks cement. Hole filled to 40' with heavy drill, 1/4 sack hulls 2nd cementing plug and 10 sacks cement to base cellar. Rat hole bridged and 5 sacks cement.

Very truly yours,

Archie Elving
 Conservation Division Agent