



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1963  
3-4-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Feb. 23, 1963.

Dear Sir:

Mr. Albert Schiffner of Forbes Caseing Pulling Co has this date requested permission to plug the following described well:

Mr. Albert Schiffner guarantees payment of the plugging fee.

Operator's full Name: THOMPSON & BEAR  
~~Forbes Caseing Pulling Co.~~

Complete Address: Box 221 Great Bend, Kansas.

Lease Name: Eads #1 Well No. #1

Location: NE-NE-NE Sec. 4 Twp. 30 Rge. 14 (E) (W) X

County Barber County Total Depth 4570' Oil Well X  
Abandoned

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Albert Schiffner was instructed to plug the well as follows:

4561' of 5 1/2" long string cemented with 75 sacks cement.  
Hole sanded to 4550' 7 5 sacks cement. 4034' of 5 1/2" long  
string pulled. 316' of 8 5/8" surface pipe circulated with  
175 sacks cement. Hole filled to 200' with mud, 10' rock bridge  
& 20 sacks cem. Hole filled to 40' with mud, 10' rock bridge  
& 10 sacks cement to base of cellar.

Very truly yours,

*Herbert J. Gustus*  
Conservation Division Agent