



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1964
S-22-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Red Bishop of Leben Drilling Inc. has this
date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Inc.

Complete Address: 912 Central Bldg., Wichita, Kansas

Lease Name: Weede Well No. # 1

Location: C NE-NW Sec. 7 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4635 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Bishop was instructed to plug the well as follows:
320' of 8 5/8" surface pipe, cemented with 300 sacks, Fill
hole with drilling mud to 275', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cement with 10 sacks to base cellar. Bridge and cement rat
hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent