

State of Kansas



15-135-30190-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

MAY 2 - 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Leben Drilling Co has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Shell Oil Co

Complete Address: 1200 First Nat'l Bldg. OKLA. City OKLA.

Lease Name: SEKAVIE Well No. 1-18

Location: C-SW-NE Sec. 18 Twp. 20 Rge. 22 (E)(W) X

County Ness Total Depth 4365 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

Jet pits circulate hole with heavy mud, set cementing plug at 540 ft.,
and displace 25 sac cement thru drill pipe, heavy mud to 260 ft., set
cementing plug and displace 20 sac cement thru drill pipe, heavy mud
to 40 ft., set cementing plug, 1/2 sac hulls and 10 sac cement, cementing
to base of cellar. Plug rat hole with two sac cement.

Very truly yours,

Leo Massey
Conservation Division Agent