

State of Kansas



15-135-30186-0000

WM. H. AVERY Governor  
WILLIAM I. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 25 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. BURTON of Pickrell has this date requested permission to plug the following described well:

Mr. BURTON guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth Nat'l Bank Bg. Wichita, Ks.

Lease Name: Gross "A" Well No. 1

Location: C-NE-NW Sec. 18 Twp. 22 Rge. 22 (E)(W) X

County Ness Total Depth 4410 Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. BURTON was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at 540 ft..  
and displace 20 sack cement thru drill pipe, heavy mud to 250' set  
cementing plug and displace 20 sack cement thru drill pipe, heavy mud  
to 40 ft., set cementing plug, 1/2 sack hulls and 10 sack cement, cementing  
to base of cellar. Plug rat hole with two sack cement.

Very truly yours,

Geo Massey  
Conservation Division Agent