



Handwritten initials "RJ"

15-135-20234-0200

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 24 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Rodie of Rains & Williamson has this date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company

Complete Address: 410 4th National Bldg., Wichita, Kansas

Lease Name: Beltz Well No. 4395 1

Location: C NE SE Sec. 13 Twp. 20 Rge. (E)(W) 22

County: Ness Total Depth 4395 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Rodie was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
50 sk cmt thru drill pipe. Heavy mud to 540' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls nd 10 sk cmt to base of cellar. Plugged rat hole
with 2 sk cmt.

Very truly yours,

Rico J. M... ..
 Conservation Division Agent