



15-007-30209-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1966

2-8-66

CONSERVATION DIVISION
Wichita, Kansas

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
ROBT. C. LONDERHOLM, Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Howard Roberts of Strata Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc.

Complete Address: Box 797, Great Bend, Kansas

Lease Name: West Well No. # 1

Location: C SW SE Sec. 10 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4614' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

252' of 8 5/8" surface pipe, cement circulated with 200 sacks.

Fill hole with drilling mud to 250', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat and mouse holes with
4 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent