

15-007-01492-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1963

2-27-63
CONSERVATION DIVISION
Wichita, Kansas

Thompson

Operator's Full Name Thompson And Bear

Complete Address: 335 Union Center Bldg., Wichita, Kansas

Lease Name Eads Well No. # 2

Location SW NE NE Sec. 4 Twp. 30 Rge. 14 (E) (W)

County Barber Total Depth 4554

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Co.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 3:00PM Day 24th Month Feb. Year 1963

The Above well was plugged as follows:

264' of 8 5/8" surface pipe cement circulated. 4549' of 5 1/2" long string
cemented with 75 sacks. Perferated from 4528' to 4532'. Sanded to 4515'
cemented with 5 sacks. Hole was filled with mud to 200'. 10' rock bridge
cemented with 20 sacks. Hole filled to 40' with mud. 10' rock bridge
cemented with 10 sacks to base cellar.
4035' of 5 1/2" long string recovered from hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audine Elving
Well Plugging Supervisor

DATE 2/28/63

INV. NO. 6651-W