

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials and signature

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 100-38

LOCATION NE-NE-NW

SEC. 4 TWP. 30 RGE. 14-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Putman

Operator Walt Co. of Refinery, Inc. Address 320 W. N. Blvd. - Wichita - Kans.

Field _____ County Boone

Total Depth 4678 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 5 7/8 - 785 ft. Circulated with cement.
3 1/2 casing set at 4678 ft. 100 sacks of cement.
Plugged back to 4617 ft. with mud & cement - Baker Plug at
4617 - Perforated at 4581 to 4595 & cemented with 250 sacks of
cement. Dumped 5 sacks of cement at 4577 ft. Shot off &
pulled the 3 1/2 casing - mud to 250 ft. Set Rock Bridge
& 15 sacks of cement at 250 ft. - mud to 30 ft. Plug &
10 sacks of cement at the surface.
West Supply - Plugging Contractors*

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1951

C. H. Stoenck
District Conservation Agent

Date 8-14-51

PLUGGING
FILE SEC 4 T 30 R 14W
BOOK PAGE 100 LINE 38

CONSERVATION DIVISION
Wichita, Kansas
8-17-51