

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15135-30187-0000

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Gross "A" Well No. 1

Location 150' -W C SE NW Sec. 18 Twp. 20 Rge. (E) (W) 22

County Ness Total Depth 4344'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 1 P Day 2 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 4344' 8 5/8 csg set at 247' cwc 150 sk.

5 1/2 csg set at 4334' cw 150 sk cmt

Set 5 1/2 wood plug at 4000' -poured 15' sd -dumped 5 sk cmt W/dump bailer. (3950-4000)

Cutoff and recovered 500' of 5 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water W/200 lbs hulls, released 8 5/8 plug

and pumped 100 sk 50-50 poz cmt 6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Lois F. Mearns
Well Plugging Supervisor

INVOICED

DATE 6-7-72

INV. NO. 5828-42