

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

JAN 17 1966  
1-17-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Leben Drilling, Inc.

Complete Address: 815 Wichita Plaza, Wichita, Kansas

Lease Name Basye Well No. # 1

Location C NW SW Sec. 17 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4710'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza, Wichita, Kansas License No.     

Operation Completed: Hour 9:00 AM Day 16th Month Jan. Year 1966

The Above well was plugged as follows:

307' of 8 5/8" surface pipe, cement circulated with 275 sacks. Hole  
was filled with drilling mud to 275', 1st cementing plug, bridged solid  
with dry cement and hulls on fluid at 275', and cemented with 25 sacks.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged  
solid with dry cement and hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat hole bridged and cemented with  
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/17/66  
INV. NO. 2612-4

Signed: Archie Elving  
Well Plugging Supervisor