

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

FEB 8 1966
2-8-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Inc.

Complete Address: Box 797, Great Bend, Kansas

Lease Name West Well No. # 1

Location C SW SE Sec. 10 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4614'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Strata Drilling, Inc.

Address: 2421 Tenth St., Great Bend, Kansas License No. _____

Operation Completed: Hour 4:00 AM Day 7th Month Feb. Year 1966

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cement circulated with 200 sacks. Hole
was filled with drilling mud to 250', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 250', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with 10
sacks to the base of the cellar. Rat and mouse holes bridged and cement-
ed with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/8/66
INV. NO. 2694-4