



15-135-26093-0000  
A J

ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 12 1967  
12-13-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Musgrove of Hellar Drlg. Co. has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Hellar Drlg. Co., Inc.

Complete Address: 1014 Union Center Wichita, Kansas

Lease Name: Mellick Well No. 1

Location: C SW SW Sec. 35 Twp. 18 Rge. 21(E)(W) X

County: Ness Total Depth 4282 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Musgrove was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 660' and displace  
100 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,  
  
Leo J. Massey  
Conservation Division Agent