



15:135:21410-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1977
12-27-77
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of DNB Drlg. has this
date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Brooks Hall Oil Corp.

Complete Address: 101 Park Ave., Suite 600, Oklahoma City, Okla.

Lease Name: Schwartz Well No. 1

Location: SE SE Sec. 13 Twp. 19 Rge. (E)(W) 22

County: Ness Total Depth 4372' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 600' thru drill
pipe. Heavy mud to 270' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent