



15135-20797-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Delaney of R & W Drlg. has this
date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Wichita Iron & Metal Corp.

Complete Address: Box 13021 Wichita, Ks.

Lease Name: Schwein Well No. 1

Location: C: NW SE Sec. 13 Twp. 19 Rge. (E)(W) 22

County: Ness Total Depth 4390' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Delaney was instructed to plug the well as follows:
Gun pits. circulate heavy mud, set cementing plug at 500' and displace
50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Bea F. Wussler
Conservation Division Agent