



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 APR 1 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Texaco Inc. has this date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name: W. F. Wilson Well No. 1

Location: NE NE NE Sec. 3 Twp. 34 Rge. 29 (E) (W)

County: Meade Total Depth 5890' Oil Well X

Gas Well Input Well AWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

10 3/4" to 1519' circulated w/ cement. 7" to 5890' cemented.

Top perforations 5242' Plug bottom w/ 50 sacks cement

Top of cement 5100' Mud 5100' to 900'

Spotted 40 sacks cement 900' to 800' Mud 800' to 30'

Plug, Halls & 10 sacks cement 30' to 0'.

Very truly yours,

Edgess E. Evers
 Conservation Division Agent