



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Spector of Spector Pipe has this

date requested permission to plug the following described well:

Mr. Spector guarantees payment of the plugging fee.

Operator's full Name: Spector Pipe & Supply Inc.

Complete Address: Box 169, Russell, Kansas

Lease Name: D.J.Kolb Well No. 1

Location: NE NE NW Sec. 3 Twp. 34 Rge. 29 (E)(W)

County: Meade Total Depth 5924' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Spector was instructed to plug the well as follows:

8 5/8" to 1495' circulated w/ cement. 5 1/2" to 5920' cemented.

Top perforations 4579' Plug, bottom w/ 20 sacks cement.

Top of cement 4505' Mud 4505' to 1000'

Spot 30 sacks cement 1000' to 900' Mud 900' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Edson J. Evers  
Conservation Division Agent