

State of Kansas



15-135-20848-0000

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

FEB 19 1974

CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of DNB Drlg. has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.Operator's full Name: Zenith Drilling Corp.Complete Address: 200 W. Douglas, Wichita, Ks.Lease Name: Rehr Well No. 4410Location: C SE NW Sec. 17 Twp. 19 Rge. (E)(W) 22County: Ness Total Depth 4410 Oil Well Gas Well  Input Well  SWD Well  D & A XX Lost Hole Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace  
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

  
Conservation Division Agent