



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company, has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Reinhardt Well No. D-1

Location: CSW-NE Sec. 2 Twp. 20 Rge. (E)(W) 22

County: Ness Total Depth 4450' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

275'--8 5/8" Surface Pipe, cement circulated with 160 Sx.

Circulate hole with heavy mud. Pull DP to 550' and displace 70 Sx. cement plus 6% gel thru DP. Pull DP to 275' and displace 20 Sx. cement plus 6% gel thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent