

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1965
6-1-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Hopkins of Aylward Drilling Co. has this
date requested permission to plug the following described well:

Mr. Hopkins guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Company

Complete Address: 909 First National Bank Bldg., Wichita, Ks

Lease Name: Skinner "F" Well No. # 2

Location: SW NE NE Sec. 1 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4539' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hopkins was instructed to plug the well as follows:

175' of 8 5/8" surface pipe, cement circulated with 175 sacks.
Fill hole with drilling mud to 190', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent