

RECEIVED  
STATE CORPORATION COMMISSION

KANSAS

FORM CP-3  
Rev. 1-8-82

OCT 01 1982

STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas  
CONSERVATION DIVISION AGENT REPORT

API Number 15-135-22,295-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Southerland Bldg. Inc. #5551

Complete Address 212 N. Market Suite 400 Wichita, Ks.

Lease Name F005 Well No. 1

Location SW-NE Sec. 1 Twp. 20 Rge. 22 (East)(West)

County Ness Total Depth 4420

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mallard Drly. Co.

Address 405 Century Plaza Wichita, Ks. 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 5:30 PM Day: 27 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" s.p. to 501' w/ 325 sx 60/40 Pozmix 2% gel-3% cc

Order: 125 sx 50/50 Pozmix 4% gel-3% cc + plug

1st plug @ 900' w/ 50 sx

2nd plug @ 510' w/ 50 sx

3rd order bridge @ 40' → cement to 0' w/ 10 sx

5th Rathole w/ 10 sx

6th Manhole w/ 5 sx

*Cement by ALLIED*

Amount of Surface Casing: 510'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Summit  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

INVOICED

DATE 10-20-82

INV. NO. 1458-W