

15-007-30129-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1965
7-23-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Aylward Drilling Company

Complete Address: 909 First National Bank Bldg., Wichita, Kansas

Lease Name Skinner "F" Well No. # 1

Location ~~SW NW SW~~ SW NE SE Sec. 1 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4405'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 11:00AM Day 21st Month July Year 1965

The Above well was plugged as follows:

124' of 8 5/8" surface pipe, cement circulated. 4404' of 5 1/2" long string,
cemented with 50 sacks. This is an open hole. Bottom of the hole was
sanded to 4400', and cemented with 5 sacks. 3600' of 5 1/2" long string was
recovered from the hole. Hole was filled with mud to 150'. Bridge plug
set at 150', and 10' of rock bridge, and cemented with 30 sacks, bringing
the top of the cement to 103', in the surface pipe. Hole was filled with
mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the
base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/26/65

INV. NO. 1513-W