

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1965

6-1-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drilling Company

Complete Address: 909 First National Bank Bldg., Wichita, Kansas

Lease Name Skinner "F" Well No. # 2

Location SW NE NE Sec. 1 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4539'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Aylward Drilling Company

Address: 909 First National Bank Bldg., Wichita, Ks. License No.

Operation Completed: Hour 5:45 PM Day 28th Month May Year 1965

The Above well was plugged as follows:

175' of 8 5/8" surface pipe, cement circulated with 175 sacks. Hole
was filled with drilling mud to 190', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 190', and cemented with 25 sacks,
bringing the top of the cement to 135' in the surface pipe. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged solid with
dry cement and hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6/2/65
INV. NO. 1251-W

Signed: Archie Elving
Well Plugging Supervisor