

Handwritten initials and a large scribble, possibly 'CP3' and a large 'B' or similar symbol.

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 11-13

LOCATION E. NW. NW

SEC. 1 TWP. 31 RGE. 14-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease Marjorie

Operator Phillips Wyo. Co. Address Box 779 - St. Bend - Kansas

Field \_\_\_\_\_ County Barber

Total Depth 4430 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 809ft Circulated with Cement  
Plugged back from bottom to 4250ft. Set Plug &  
5 Sacks of Cement in 3/4" casing at 4250ft. Shift off &  
Pulled 2200ft of 3/4" casing - Filled with mud to 809ft  
Bridge & 15 Sacks of Cement - Mud to 200ft - Bridge &  
15 Sacks of Cement - mud to 25ft - Plug & 15 Sacks Cement.  
Herb Heibel - Plugging - Contractor

C. H. Stough -  
District Conservation Agent

Date 4-28-48

**PLUGGING**  
FILE SEC 1 T 31 R 14W  
BOOK PAGE 11 LINE 13

APR 29 1948  
4-29-48