



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Raymond Oil Co Inc

Complete Address 200 W Douglas Wichita, KS

Lease Name Lenkner Well No. 1

Location C NW/SE Sec. 28 Twp. 32 Rge. 11 (E) (W) W

County Barber Total Depth 4823

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Voth Casing Pulling Co

Address 715 S Ave Arkansas City, KS License No. 684

Operation Completed: Hour 2:00 PM Day 26 Month 11 Year 1974

The above well was plugged as follows:

283 ft 9 5/8 surface cemented with 175 sacks. 2253 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 1916 ft. Sand to 1900 ft,
5 sacks cement with bailer. Pulled 1480 ft 5 1/2. Set 10 ft rock
bridge at 370 ft. Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 12/4/74

INV. NO. 396-W