

KANSAS

SP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1972
11-30-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Raymond Oil Co. Inc

Complete Address 200 W Douglas Wichita, Ks

Lease Name Lukens Well No. 1

Location SW/SW/NE Sec. 28 Twp. 32 Rge. 11 (E) (W) W

County Barber Total Depth 4860

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 4:00 PM Day 28 Month 11 Year 1972

The above well was plugged as follows:

328 ft 9 5/8 surface pipe cemented with 300 sacks. 4859 ft 5 1/2 long

string cemented with 100 sacks. Top per. 4144 ft. Sand to 4100 ft,

5 sacks cement with bailer. Pulled 3460 ft 5 1/2. Set 10 ft rock bridge

at 360 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. Russell Biberstein*
Well Plugging Supervisor

DATE 11/30/72
INV. NO. 6680-W