

16
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1965
10-25-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Eli Wilkerson

Complete Address: 11th Floor, Philtower Bldg., Tulsa, Oklahoma

Lease Name Skinner Well No. # 1

Location SE SE SW Sec. 20 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4770'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 3:15 PM Day 22nd Month Oct. Year 1965

The Above well was plugged as follows:

313' of 8 5/8" surface pipe, cement circulated. 4770' of 5 1/2" long string,
cemented with 75 sacks. Plug back to 4400'. Top perferation 4375'. Bottom
of the hole was sanded to 4360', and cemented with 5 sacks. 3400' of 5 1/2"
long string was recovered from the hole. Hole was filled with mud to 300',
bridge plug and rock bridge from 300' to 290', and cemented with 25 sacks.
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 10/26/65
INV. NO. 2043-11