

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1965
7-19-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: P. O. Box 432, Liberal, Kansas

Lease Name Lora Mills "H" Well No. # 1

Location SE SW Sec. 32 Twp. 31 Rge. 14 (E) (W) W

County Barber Total Depth 4854'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 6:00 PM Day 16th Month July Year 1965

The Above well was plugged as follows:

800' of 10 3/4" surface Pipe, cement circulated. 4842' of 7" long string, cemented with 300 sacks. Plug back to 4080'. Top perforation 4062'. Bottom of the hole was sanded to 4050', and cemented with 5 sacks. 2000' of 7" long string was recovered from the hole. Hole was filled with mud to 300', and 10' of rock bridge, and cemented with 30 sacks. Hole was filled with mud to 40', and 10' of rock bridge, and cemented with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/20/65

INV. NO. 1487-00

Signed: Archie Elvino
Well Plugging Supervisor