

15735301510000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

SEP 18 1975  
9-18-75  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Coquina Oil Corporation  
 Complete Address Drawer 2960 Building of the Southwest, Midland, Texas 79701  
 Lease Name Borger Well No. 3  
 Location 100' E/C SW NW Sec. 25 Twp. 19 Rge. (E) (W) 22  
 County Ness Total Depth 4388'  
 Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A       
 Other well as hereafter indicated       
 Plugging Contractor Knight Casing Pulling  
 Address Box 405, Chase, Kansas 67524 License No. 436  
 Operation Completed: Hour 3 P Day 13 Month 9 Year 1975

The above well was plugged as follows:

Total Depth 4388' 8 5/8 csg set 415' cwc 250 sk.  
5 1/2 csg set 4378' cw 150 sk cmt.  
Filled 5 1/2 csg W/sd (4380-4350) dumped 5 sk cmt W/dump bailer. (4350-4315)  
Cutoff & recovered 2774' of 5 1/2 csg.  
Mixed & pumped down 8 5/8 csg --20 sk gel & water-75 sk 50-50 poz -8 sk gel &  
water- plug & 25 sk 50-50 poz.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 9-23-75  
INV. NO. 1939-W

Signed: Leo F. Massey  
Well Plugging Supervisor