

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -135 - 21,291.000 (of this well)

Operator's Full Name Mack Oil Co.

Complete Address 908 Union Center, Wichita, Kansas

Lease Name Foos Well No. 2

Location C NE NW Sec. 22 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4498'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 2:24 A Day 11 Month 3 Year 1977

The above well was plugged as follows:

RTD 4498' 8 5/8 csg set 365' cwc 200 sx. Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 250' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 3-14-77

INV. NO. 4789-W