

STATE CORPORATION COMMISSION

15135-21052-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 27 1975  
5-27-75  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mack Oil Company  
Complete Address 812 Union Center, Wichita, Kansas  
Lease Name Foos Well No. 1  
Location C SE SW Sec. 22 Twp. 19 Rge. (E) (W) 22  
County Ness Total Depth 4400'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX  
Other well as hereafter indicated       
Plugging Contractor Rains & Williamson  
Address Wichita, Kansas License No.     

Operation Completed: Hour 1 A Day 22 Month 5 Year 1975

The above well was plugged as follows:

RTD 4400' 8 5/8 csg set 346' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.  
Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 5/29/75

INV. NO. 1393-W