

15-135-20553-0000 R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 5 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Fender Pipe & Supply, Inc.

Complete Address Box 302 Russell, Kansas 67665

Lease Name Westermeyer Well No. 2

Location C SW NE Sec. 19 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4368'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 4:15 P Day 1 Month 6 Year 1972

The above well was plugged as follows:

Total Depth 4368' 8 5/8 csg set at 346' cwc:

5 1/2 csg set at 4362 cw 100 sk cmt. Sand back 5 1/2 csg to 4345-dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 2814' of 5 1/2 csg. Sand back to:

Pumped down 8 5/8 csg with 200 lbs hulls, 16 sk gel & water, released 8 5/8 plug,

pumped 85 sk cmt, 8 sk gel & water, & capped 8 5/8 csg with 15 sk cmt W/100 lbs hulls.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red P. Murray
Well Plugging Supervisor

DATE 6-6-72

INV. NO. 5819-u