

15735-20557-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 21 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Circle Oil Company & United Petroleum Co.

Complete Address 500 Bitting Bldg., Wichita, Kansas

Lease Name Schlegel Well No. 1

Location C SE SE Sec. 18 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4385'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Sage Drilling (Rotary)

Address Wichita, Kansas License No.       

Operation Completed: Hour 12 M Day 18 Month 1 Year 1972

The above well was plugged as follows:

RTD 4385' 8 5/8 csg set at 338' cwc. Cmt. Mat. 50-50 poz cmt W/6% total Gel.  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mansery  
Well Plugging Supervisor

DATE 1-21-72

INV. NO. 5052-W