

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

15135-20848-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zenith Drilling Corp.
Complete Address 200 W. Douglas, Wichita, Kansas
Lease Name Rehr Well No. 4410
Location C SE NW Sec. 17 Twp. 19 Rge. (E) (W) 22
County Ness Total Depth 4410'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor DNB Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 8 P Day 11 Month 2 Year 1974

The above well was plugged as follows:

RTD 4410' 8 5/8 csg set at 326' cwc Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 2/20/74INV. NO. 8597-U