

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

K

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-135-22,056-0000

Operator's Full Name TWIN LASTEREN RESOURCES, INC.

Complete Address 922 UNION CENTER, WICHITA, KANS. 67202

Lease Name MARGHEIM Well No. #1

Location C-SW-NW Sec. 14 Twp. 19 Rge. 22 (East) (West)

County NESS Total Depth 4460 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor THUNDERBIRD DRILLING, INC

Address 7701 EAST HELLOGG #780, WICHITA, MO. License No. _____

Operation Completed: Hour: 8:00 AM Day: 9th Month: JULY Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8" 345 FT SB. CUL. w/ 225 FT COMMON - 2% GEL - 3% CA-CL.
ORDERED 110 FT 5 1/2" PERMIX 4% GEL - 3% CA-CL. + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG @ 180 FT w/ 65 FT CMT.
2ND PLUG @ 360 FT w/ 30 FT CMT.
3RD PLUG - SOLID BRIDGE - HULL'S - PLUG @ 40 FT TO 110 FT w/ 10 FT CMT.
5 FT IN RAT HOLE

CEMENTED BY ALLIED CMT.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

Signed: Marion Schmidt
Conservation Division Agent

INVOICED

DATE 8-26-81

INV. NO. 6325-W

III 13 1981
7-13-81
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

August 26, 1981

INVOICE NUMBER: 6325-W

TO: Twin Western Resources, Inc.
922 Union Center
Wichita, KS. 67202

PAYABLE UPON RECEIPT

PLUGGING ASSESSMENT AS FOLLOWS:

Margheim #1

C SW NW, Sec.14-19S-22W

Ness

Thunderbird Drilling, Inc.

T.D. 4400

\$143.00

NOTE: We also need the following before our file is completed:

- _____ Well Plugging Record (CP-4)
- _____ Well Log
- _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

For Administrator



Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS., 67601

is hereby assigned to supervise the plugging of the above mentioned well.