

15135-20137-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name D. R. Lauck Oil Company, Inc.

Complete Address: 301 S. Broadway Wichita, Kansas

Lease Name McCreight Well No. 1

Location C NE SW Sec. 7 Twp. 20 Rge. 22 (E) (W)

County Ness Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: _____ Co. Tools: _____

Address: _____ License No. _____

Operation Completed: Hour 11:15P Day 12 Month 4 Year 1968

The Above well was plugged as follows:

RTD 4450' 8 5/8 csg set at 312' cwc 180 sc.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mussey
Well Plugging Supervisor

DATE 4/15/68

INV. NO. 7574-W