

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 29 1966  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bowers Drilling Company

Complete Address: 416 Union Center Bldg., Wichita, Kansas

Lease Name Lonker Well No. "D"

Location C S/2 NW Sec. 36 Twp. 32 Rge. 13 (E) (W) W

County Barber Total Depth 4548'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Clarke Corporation, Inc.

Address: Chapin Bldg., Medicine Lodge, Kansas License No. 583

Operation Completed: Hour 4:15 PM Day 28th Month July Year 1966

The Above well was plugged as follows:

290' of 8 5/8" surface pipe, cemented with 200 sacks. 4548' of 4 1/2" long  
string, cemented with 200 sacks. Top perforation 4454'. Bottom of the hole  
was sanded to 4425', and cemented with 3 sacks. Pipe was dropped and lost  
in the hole. No pipe was recovered from the hole. Fluid in the hole was  
bailed down to 275', rock bridge from 275' to 265', and cemented with 25  
sacks. Hole was filled with mud to 40', rock bridge from 40' to 30', and  
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving  
Well Plugging Supervisor

INVOICED

DATE 7/29/66  
INV. NO. 3651-u