

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name G. S. Lonker Well No. # 3

Location C SW SW Sec. 36 Twp. 32 Rge. 13 (E) (W) W

County Barber Total Depth 3866

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 2:00PM Day 4th Month May Year 1964

The Above well was plugged as follows:

520' of 8 5/8" surface pipe, cemented with 300 sacks. 3849' of 5 1/2" long
string, cemented with 150 sacks. Bottom of the hole was sanded to 3830',
and cemented with 20 sacks. Hole was bailed down to 300', Plug was set
at 300', with 10' of rock bridge, and cemented with 25 sacks. Hole was
filled with mud to 40', with 10' of rock bridge, and cemented with 10
sacks to base cellar.

2782' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/5/64

INV. NO. 9095-U

Signed: Archie Elving
Well Plugging Supervisor