

15-135-20230-0000

SR

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Co. Inc.

Complete Address: 1125 Wichita Plaza Wichita, Kansas 67202

Lease Name Gillig Well No. 1

Location NE SE SE Sec. 26 Twp. 19 Rge. (E) (W) 22

County Ness Total Depth 4406

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling Inc.

Address: Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 3:30P Day 17 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4406' 8 5/8 csg set at 314' cwc

5 1/2 csg set at 4395' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (4300-4406) Dumped 5 sk cmt. W/dump bailer. (4260-4300)

Shotoff and recovered 2800' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 10 sk gel W/2 sk hulls, plug and 130 sk

50-50 poz cmt. W/6% total gel. Max. pres. 500 lbs. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5-19-69

INV. NO. 9792-W