

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

NOV 21 1962

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Bud Hodkins of Alyward Drilling Co. has this date requested permission to plug the following described well:

Mr. Hodkins guarantees payment of the plugging fee.

Operator's full Name: BOWERS DRG. INC. & N. C. R. A.
Alyward Drilling Co.

Complete Address: 416 Union Center Bldg.
~~813 First National Bank Bldg.~~ Wichita, Kansas.

Lease Name: Lonker "A" #1 Well No. #1

Location: C-NE-SW-NE Sec. 35 Twp. 32 Rge. 13 (E) (W) X

County Barber Total Depth 4660' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hodkins was instructed to plug the well as follows:

419' of surface pipe (8 5/8"), circulated with cement (300 sacks)

Hole filled to 200' with heavy drill mud, 1/4 sack hulls, 1st

cementing plug and 20 sacks cement by Globe Cementing Co.

Hole filled to 40' with heavy drill mud, 1/4 sack hulls, 2nd

cementing plug and 10 sacks cement to base of cellar. Rat
hole bridged and 2 sacks cement.

Very truly yours,

Hessman Justus
 Conservation Division Agent