

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Lenoard Goodenough of J. M. Huber Corporation has this date requested permission to plug the following described well:

Mr. Goodenough guarantees payment of the plugging fee.

Operator's full Name: J. M. Huber Corporation

Complete Address: 5415 N. Pennsylvania, Oklahoma City, Okla.

Lease Name: Hopkins Well No. # 1

Location: NW SW SE Sec. 28 Twp. 32 Rge. 13 (E)(W) W

County Barber Total Depth 4505' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Goodenough was instructed to plug the well as follows:

300' of 8 5/8" surface pipe, cement circulated with 300 sacks.

Fill hole with drilling mud to 295', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent