

State of Kansas



12

15-135-20292-0000

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Engel of Slawson Drlg. has this
date requested permission to plug the following described well:

Mr. Engel guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Ks.

Lease Name: Schaben "B" Well No. 1

Location: 140' N of C NW NE Sec. 24 Twp. 19 Rge. (E)(W) 22

County: Ness Total Depth 4380' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Engel was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 650' and displace

50 sk cmt thru drill pipe. Heavy mud to 400' set cementing plug and

displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. J. Marney
Conservation Division Agent