

DRILLERS LOG

FARM NAME: Baker
 COMPANY: J.M.HUBER CORPORATION
 CONTRACTOR: J.M.HUBER CORPORATION

LOCATION: NE NE NE,
 Sec. 17-30S-14W,
 Barber County, Kansas

COMMENCED: 5-25-47
 COMPLETED: 6-15-47

PRODUCTION: Dry & abandoned.

CASING USED: 10-3/4" @ 1075 w/ 450 sx.

Shale & sand	100
Red bed & shells	850
Red bed & shale & shells	1085
Shale & shells-Red beds	1185
Shale & shells	1275
Salt & shells	1550
Shale & shells	1740
Lime streaks	1925
Broken lime	2045
Lime & shale	2430
Lime & shale streaks	2530
Shale & shells	2600
Shale	2700
Lime & shale	2875
Shale & lime shells	3010
Lime & shale	3525
Broken Lime & shale	3580
Sandy lime-Sand	3630
Lime	3635
Lime & shale	3677
Shale & sand streaks	3830
Lime & shale	3955
Lime	4205
Lime & shale	4300
Lime	4350
Lime & shale	4420
Lime	4447
Lime & shale	4480
Lime shale & chert.	4505
Chert	4538
Sandy Lime	4558
Sand & shale	4635
Lime & shale	4705
Total Depth	4705

SAMPLE TOPS:

Top Anhydrite	805
Top Lansing	3987
Top Conglomerate	4485
Top Residual Viola Chert.	4505
Top Simpson	4538
Simpson Sand	4540-58, very little por. & very slight staining.
HDST	4540-58, open 30 min. rec. 60' mud, 90' salt water.
Second Simpson Sand	4601-09, fair porosity & stain.
HDST	4601-22, open 30 min. rec 15' mud.
Arbuckle	4654
HDST	4665-4705, WD. open 30 min. rec. 3300' sulphur water.

Ran Schlumberger. Dry & abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

7-7-47

I hereby certify that the above is a true and correct copy of the log of the Baker No. 1 located in the Northeast Quarter of the Northeast Quarter of the Northeast Quarter of Section 17, Township 30 South, Range 14 West, Barber County, Kansas.

Edward A. Huffman
 Edward A. Huffman
 District Manager, J.M.HUBER CORPORATION

Subscribed and sworn to before me this 3rd day of July 1947.

Annelle Syrell
 Notary Public.

My Commission expires June 7, 1950.

PLUGGING
 FILE SEC 17-30-14W
 BOOK 116 17