

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barber SEC. 16 TWP. 30S RGE. 14 W
 Location as in quarters, or footage from lines:
 S.E. ~~N.E.~~ NW AMB YCC

Lease Owner Maurice L. Brown
 Lease Name Standard Well No. 1
 Office Address Box 11320/Kansas City, MO/64112
 Character of Well (Completed as Oil, Gas or Dry Hole): oil
 Date Well Completed 03/31/78
 Application for plugging filed 03/15/83
 Plugging commenced 03/22/83
 Plugging completed 05/05/83
 Reason for abandonment of well or producing formation dry

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 4750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	501	none
				5 1/2	4634	2197

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Plugged back at 3336

Sand from 3336 to 3260
5 sx cement dumped with dump bailer from 3260 to 3230
Ripped pipe at 2197
Sun Cementing
15 hull, 15 jell, 50 cement, 10 jell, 1 hull, dropped plug.
150 cement, 50-50 POZ, 2% jell, 3% c.c.

Zimmerman & Metz on location

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corp.

STATE OF Kansas COUNTY OF Barber, ss.
Elmer R. Morgenstern (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Elmer R. Morgenstern
Medicine Lodge, KS
 (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of May, 1983.

Jessie Hamilton
 Notary Public.

My Commission expires: April 4, 1986

RECEIVED
 STATE CORPORATION COMMISSION

MAY 17 1983
 5-17-83
 CONSERVATION DIVISION
 Wichita, Kansas

15-007-20545-0000

OPERATOR: The Maurice L. Brown Co.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Stannard #1
 LOCATION: C SE NW Section 16-30S-14W
 Barber County, Kansas
 SPUD DATE: October 22, 1977
 COMPLETION DATE: November 8, 1977

0	285	Top soil, sand & shale
285	744	Sand, shale, red beds
744	1177	Shale, red beds
1177	1970	Red bed & shale
1970	2562	Shale & lime
2562	2720	Lime & shale
2720	2990	Shale & lime
2990	3205	Lime & shale
3205	3344	Shale & lime
3344	3520	Lime & shale
3520	3845	Shale & lime
3845	3975	Lime & shale
3975	4181	Shale & lime
4181	4258	Lime & shale
4258	4344	Lime
4344	4547	Lime & shale
4547	4568	Shale & lime
4568	4584	Lime & shale
4584	4617	Shale & lime
4617	4699	Lime & shale
4699	4750	Lime
	4750	Rotary Total Depth

Spud hole at 7:30 p.m., October 22, 1977. Drilled 776' of 12 1/4" hole. October 24, 1977, drilled 1,000' of 12 1/4" hole, ran 13 joints of 8-5/8" - 23# surface casing. Set at 501', cemented with 450 sacks Halliburton cement, 3% CaCl, 2% gel. Plug was down at 3:45 p.m., October 23, 1977.

T.D. 4570'. Ran 121 joints of 5 1/2" casing. Set at 4634'. Cemented with 325 sacks cement. Job complete at 8:45 p.m., November 8, 1977.

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Stannard #1, C SE NW Section 16-30S-14W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge,
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 14th day of November, 1977.
 NOTARY PUBLIC
 My commission expires July 21, 1979.

RECEIVED
 STATE CORPORATION COMMISSION
 Sandra Richman, Notary Public
 CONSERVATION DIVISION
 Wichita, Kansas
 12-22-82