


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 16 Twp. 30S Rge. 14W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C S/2 SW NE

Lease Owner Braden-Deem, Inc.
Lease Name DURALL Well No. 1
Office Address 200 E. First Street, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Date Well completed Dec. 21 1979
Application for plugging filed (verbally) Dec. 21 1979
Application for plugging approved (verbally) Dec. 21 1979
Plugging commenced Dec. 21 1979
Plugging completed Dec. 21 1979

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4606'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. 4606'

Set 1st plug at 270' with 40 sacks

2nd plug at 40' to mud with 10 sacks, 1/2 sack of hulls
rathole with 5 sacks.

Cemented with 50/50 posmix, 6% gel.

Plug was down at 10:30 p.m., 12-21-79.

RECEIVED
STATE CORPORATION COMMISSION
JAN 7 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Jack L. Partridge

801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 19 80



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

CONTRACTOR'S WELL LOG

OPERATOR: Braden-Deem, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Durall #1
 LOCATION: C S/2 SW NE, Section 16-30S-14W
 Barber County, Kansas
 SPUD DATE: December 13, 1979
 COMPLETION DATE: December 21, 1979

0	476	Top soil and red beds
476	1000	Red beds
1000	1885	Red beds and shale
1885	4606	Lime and shale
	4606	Rotary Total Depth

Spud hole at 10:15 a.m., December 13, 1979. Drilled a 12 1/4" hole. Ran 7 joints of 8-5/8" new 20# casing. (Talley 278.35'). Set at 288' with 250 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 12:00 midnight, December 13, 1979.

T.D. 4606'. Set 1st plug at 270' with 40 sacks, 2nd plug at 40' to mud with 10 sacks, 1/2 sack of hulls and the rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 10:30 p.m., December 21, 1979.

SAMPLE TOPS:

Anhydrite 1319'
 B/Anhydrite 1331'

RECEIVED
 STATE CORPORATION COMMISSION
 1-7-80
 JAN - 7 1980
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Durall #1, C S/2 SW NE, Section 16-30S-14W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 3rd day of January, 1980.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.